Annexure J: Copy of the RTI reply from the Chief Engineer, W.R.D.O

್ರಜಿನಿಯರ್ ರವರ ಕಛೇರಿ ಕ್ಸ್ಪೌಪನ್ಮೂಲ ಅಭಿವೃದ್ಧಿ ಸಂಸ್ಥೆ ,ದರಾವು ವೃತ್ತ ಗಳೂರು - 560 009

By Read pet will ಸಂಖ್ಯೆ: ಜಸಅ:ಯೋಮತಃಟಿಎ-4:ಸಇ-3:ಮಾಹಿತಿ ಹಕ್ಕು:2007-08

ಕಛೇರಿ : 22871094, 22875519

22871174, 22352430

ಫ್ಯಾಕ್ಸ್ : 080-22872247

080-22204528

18 MAR 2008

ಇ-ಮೇಲ್ : bngwrdo@kar.nic.in

ದಿನಾಂಕ..9-03-08:-----TR

ಇಘರಗೆ,

ಶ್ರೀ ಅರ್ಪಿತಾ ಜೋಷಿ, ನಂ.105, ಈಸ್ಟ್ ಎಂಡ್ 'ಬಿ' ಮುಖ್ಯ ರಸ್ತೆ, 9ನೇ ಬ್ಲಾಕ್, ಜಯನಗರ, ಬೆಂಗಳೂರು 560 069.

ಮಾನ್ಯರೆ,

ವಿಷಯ:- ಮಾಹಿತಿ ಹಕ್ಕು ಅಧಿನಿಯಮದಡಿ 2005ರಂತೆ ಕಬಿನಿ ಜಲಾಶಯದ ಮಾಹಿತಿ ಒದಗಿಸುವ ಕುರಿತು. ಉಲ್ಲೇಖ:- ತಮ್ಮ ಡಿ.ಡಿ. ಪತ್ರದ ದಿನಾಂಕ: 6-3-2008.

ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ಕಬಿನಿ ಜಲಾಶಯ ಯೋಜನೆಯ ಪರಿಷ್ಕೃತ ಅಂದಾಜು ವರದಿ ಹಾಗೂ ಕಬಿನಿ ಜಲಾಶಯದ ನೀರಿನ ಒಳ ಹಾಗೂ ಹರಿವಿನ ವರದಿಯನ್ನು ಇದರೊಂದಿಗೆ ಕಳುಹಿಸಲಾಗಿದೆ.

ಅಡಕ: 14 ಪುಟ.

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

K. Sul saman ಸಾರ್ವಜನಿಕ ಮಾಹಿತಿ ಅಧಿಕಾರಿ, ಜ.ಸಂ.ಅ.ಸಂಸ್ಥೆ, ಬೆಂಗಳೂರು.

CAUVERI NEERAVRI NIGAMA LIMITED

(A Government of Karnataka undertaking)

REPORT OF

KABINI RESERVOIR PROJECT AS PER PROJECT REPORT OF REVISED ESTIMATE OF RS. 1233 CORES)

brief mote on revised estimate of

KABINI RESERVOIR PROJECT

The Kabini project as per original proposal was contemplated to impound 12.30 Time, of water to irrigate an area of 30,000 acres at an lift canals in two seasons). The total cost of the Kabini Project worked of to Rs.390 Crores and the same was Administratively approved vide G No. PWD 22 MKB 81, Bangalore, dated 24/06/1986.

THIRD REVISION: PROPOSED FOR RS. 1,233 CRORES (2003):

The sanctioned Revised Project Estimate (1986) for Rs.390 Crores envisaged the construction of two additional reservoir and which was based on preliminary studies. When detailed surveys and investigation for both the reservoirs and the lift component, was taken-up, it was revealed that, part of the submergence area under Sagare Doddakere dam and the entire Submergence area under Upper Nugu reservoir lie in the jurisdiction of "The Project Tiger" and permission was not granted by the Forest Department, even for conducting surveys under the Wild Life Protection Act 1972. In addition there was stiff agitation by the villagers of re-habilitated colonies of existing Kabini Dam, which would also submerge, for construction of additional reservoirs. Hence, further survey works in this regard had to be stopped.

Subsequently, several alternative proposals were examined to cater for drought prone areas by diverting the monsoon flows from the existing Kabini Reservoir and without the construction of additional storage Reservoir. Accordingly the following two lift schemes are proposed.

Bidarahalli Lift Irrigation Scheme: The Major component of Kabini Second Stage is lifting 8.62 Tmc water with static head of 42.79m (141ti) from the fore-shore of Kabini Reservoir, on the right flank near Bidarahalli village. The main canal takes off from this cistern located near Kandegala village and runs parallel to the existing Kabini Right Bank Canal at higher margin for a length of 232 Kms. and tails off in Hebbahalla in Yelandur Taluk to irrigate 1,09,547 Acres in Khariff season only. Another Branch Canal takes off from this system and runs parallel to the periphery of the reservoir for a length of 24 Kms. to irrigate 5800 acres.

Antharasanthe Lift Irrigation Scheme:

Antharasanthe Lift freigation Scheme is proposed to lift 0 508 tm of water from the fore-shore of Kabini Reservoir on the left flank with static head of 60,96m (200 ft.) to irrigate 8000 acres of Khariff Semi-d crops.

Other Lift Irrigation Schemes:-

In the present proposal the following other Five Lift Irrigation Schemes are also included.

- 1. Taraka lift Irrigation Scheme
- 2. Nugu Lift Irrigation Scheme
- 3. Badanavalu Lift Irrigation Scheme
- 4. Hirekere- Honganur Lift Irrigation Scheme
- 5. Bannahalli hundi Lift Irrigation Scheme.

The total water requirement for Kabini project including all the above component comes to 52.00 Time, and the taluk-wise atchkat Kabini Project are as follows:

(Atchket in Acres)

SL	No. Name of the Taluk	Flow System	Lift system	Total	
1.	Heggadaevanakote.	7400	27900	35300	
2.	Nanjangud.	17000	41797	58797	
3.	T Narasipura.	29506	2400	31906	
4.	Gundulpet.	and a	250	250	
5,	Chamarajanagar.	3400	47000	50400	
6,	Kollegal.	36694	. .	36694	
<u>7.</u>	Yelandur.	16000	4000	20000	
	TOTAL:	110000	123347	233347	

7. ESTIMATED COST.

7.1 The total estimated cost of the project is Rs. 1233 Crores, which includes Rs.531 Crores for the flow component and Rs. 702 Crores for the Lift component. In respect of the flow component, the cost is as per actual for the works already executed and Schedule Rates for 2001-02 for the balance works to be done. In respect of the Lift component, the entire estimate is based on the Schedule of Rates of Kabini & Varuna Canal Circle for the year 2002-03. The total expenditure of Kabini Project (flow system only) to end of March-2003 is Rs. 389 Crores.

The revised estimate of Kabini Resorvior Project has been placed before Technical Sub-Committee meeting of Cauvery Necravari Nigama, held on 13-11-2003 at Bangalore and the same has been cleared.

Early administrative approval to the estimate is requested.

<u>c</u>as-

Superintending Engineer, Cauvery Neeravari Nigama, Kabini and Varuna Canal Circle, Mysorc.

> Chief Engineef, anverv Neergysri Nice

Cauvery Neeravari Nigama, Irrigation (South), Mysore.

SALIENT FEATURES OF KABINI RESERVIOR PRO

L GENERAL

L. Name of the Project. Kabini Project.

2. Name of the river. Klabini River.

3. Location of the dam. Between Bidarahalli and Beechanal

in II D Kote taluk, 4 miles (6.43 Er

<u>()</u>

HL CANALS:

1) KABINI RICHT BANK CANAL

Length of Main Canal. 202 Kms.

Capacity at Head. 2289 Cusocs (54.82 Cum/Sec)

Full supply depth. 16 feet (4.88 Mins) at Head Reach.

121690 Acres

Cill level of Head Shuice. 2249 00 Feet. Gross Command Area.

Cultivable Command Area. 1,07,000 Acres

2) KABINI LEFT BANK CANAL

Length of Main Canal. 26 Kms

Capacity at Head. 99 Cusees (2.80 Cum/Sec) required

Cill level of Head Sluice. 2249.00 Feet.

Full supply depth. 4.5 Feet (1.37 Meters)

Gross Command Area. 3280 Acres. Cultivable Command Area 3000 acres.

IV. LIFT SCHEMES:

j

ì

A) Bidarahalli Lift Irrigation

1. Location. Foreshore of Kabini Reservoir

1 on the right lank near Bidarahalli village. 1

2. Length of approach canal 691 Meters.

3. Static Head. 42.79 Mars,

4. Length of rising Main. 775 Mtrs.

5. Discharge required. 1057 Cusecs.

6. Diameter of pipes for rising

main and No. of rows. 4 rows of 2.4 Mt. diameters.

7. HP required. 27,200 HP

8.. No. of pumps and HP of 16 No.s of 1700 HP+4 No.s each pump. of 1700 HP standby.

Energy required at 80% power factor.

power factor. 25.40 M W 10. Length of Main Canal 232 F. M

11. Length of branch Canal

12. Irrigable Command. : 1,15,347 Acres.

13. Cropping pattern. Ehariff - Semidry.

14. Cultivable Command Area 1,15,347 Acres.

B) ANTHARASANTHE LIFT

1. Location. : Foreshore of Kabini Reservoir on

the left flank near Antharasanthe

village.

24 K M

2. Length of approach canal 1000 Mtrs.

3. Static Head. : 61.79 Mtrs.

4. Length of rising main. 1400 Mtrs.

5. Discharge required 54.14 Cusecs.

6. Diameter and pipes for rising Main and No. of row

rising Main and No. of rows 1 Row of 1.2 Mtr.diameter.

7. H P required : 2000 H P

8. No. of pumps required and 5 No.s of 400 HP+ HP of each pump. 1 No. of 400 HP standby.

9. Energy required at 80% power factor


power factor. : 1.9 M W

10. Length of Canal. : 15 Kms.

11. Irrigable Command. : 8000 Acres.

12. Cropping pattern. : Khariff'- Semidry.

13. Cultivable command area. : 8000 Acres.



CAUVERI NEERAVRI NIGAMA LIMITED (A Government of Karnataka undertaking)

KABINI RESERVOIR PROJECT OW OUTFLOW AND UTILISATION DETAILS

KABINI RESERVOIR PROJECT (FLOW SYSTEM)

DETAILS OF INFLOW, OUTFLOW AND UTILISATION DURING THE PERIOD FROM 1997-98 TO 2007-08

													Occoping Charles	Kabing & Corana Corel Chi Conjung Corena Coral Conjung Corena Corana Conjung Corana Corana
		JATOT	44.818	44.210	34.836	39.481	34.053	30.852	24.713	32.813	35.378	34.070	711 KG 175	Kabari
UTILISATION (TMC)	PLANNED	SUMMER	13.490	14.245	4.205	8.070	0.785	0.000	0.000	5.220	8.717	4.510		
		KHARIFF	31.328	29.965	30.631	31.411	33.268	30.852	24.713	27.593	26.661	29.56		
		JATOT	31.39	31.39	31.39	31.39	31.39	31.39	31.39	31.39	31.39	31.39		
		SUMMER	14.258	14.258	14.258	14.258	14.258	14.258	14.258	14.258	14.258	14.258		
		KHARIFF	17.132	17.132	17.132	17.132	17.132	17.132	17.132	17.132	17.132	17.132	·	
	OUTFLOW NMCFT	OUTFLOW	82032	82597	69745	71119	66052	50748	22375	73321	91801	100894	114006	
	INFLOW AND OUTFLOW DETAILS IN MCFT	INFLOW	128091	132619	105844	115974	100255	78089	53441	109211	134972	133216	144429	
		Year	1997-98	1998-99	1999-2000	2000-01	2001-02	2002-03.	2003-04	2004-05	2005-06	2006-07	2007-08 (UPTO SEP.07)	
		Z .	-	2	က	4	20	9	7	80	တ	9	÷	

STATEMENT SHOWING THE MONTHWISE INFLOWS INTO KABINI RESERVOIR DURING THE PERIOD FROM 1997-98 TO 2007-08 (UPTO SEP 07)

			.H- ,											_
(ALL FIGURES IN MCFT)	ANNUAL	TOTAL	19	128091	132619	105844	115974	100255	78089	53441	109211	134972	133216	144429
IGURES		MAY	17	1481	2720	1037	2610	928	829	4599	1182	5490	1092	
(ALL F		APR	16	1250	1839	1333	3188	738	719	929	1367	828	881	
		MAR	15	1496	1194	954	913	435	209	260	1068	928	423	
		FEB	14	1613	1530	795	1544	587	445	307	741	1006	625	
		JAN	13	1116	279	260	953	878	557	315	833	984	1290	
		DEC	10	3304	2886	1591	3248	2214	1333	766	114	282	2399	
		NOV	6	6044	6531	8998	5239	4309	3020	2081	968E	4473	4605	
		OCT	8	2869	15052	8522	9214	<i>4</i> 869	8416	4652	6419	8470	0492	
		SEP	9	10689	17050	7308	16887	7214	8152	5166	6804	18043	15292	28303
		AUG	5	44197	26559	29834	31808	27120	31033	14164	39469	33581	23207	38961
		JUL	4	44727	46884	36143	24550	32451	14007	14178	23204	50985	48945	65840
		JUN	3	5187	9595	12899	15820	16417	9039	6051	23734	7272	16517	11325
		YEAR	2	1997-98	1998-99	1999-200(12899	2000-01	2001-02	2002-03	2003-04	2004-05	2005-06	2009-02	11 2007-08
	S/ No.		1	1	2	က	4	5	ပ	7	ω	6	10	11

STATEMENT SHOWING THE MONTHWISE OUTFLOWS FROM KABINI RESERVOIR DURING THE PERIOD FROM 1997-98 TO 2007-08 (UPTO SEP 07)

2006-07

2007-08

(ALL FIGURES IN MCFT) STATEMENT SHOWING THE MONTHWISE CANAL WITHDRAWALS FROM KABINI RESERVOIR DURING THE PERIOD

19 44751 44214 34365 39418 39418 32808 32808 32808 32808
MAY 17 1838 1838 1838 1813 1813 1897
APR 16 16 16 1831 1021 3 1021 3 1021
MAR 15 4690 3122 1767 1767 1905 8 1163
FEB 3656 3651 1110 1110 2053 1029 1598 1598
1377 1374 400 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
DEC 10 3187 2204 2237 2882 2882 2882 2850 2790 2790 2790
9 6065 6020 6020 60112 5901 5901 4811 4811 5601 5601
0CT 8 8 6401 6201 6217 6217 6217 6335
SEP 6 6195 6 619
640. 640. 640. 640. 640. 640. 640. 640.
JUL A JUL A JUL A 3090 38 3090 44 2971 76 540 0 743 0 743 0 2826 107 3455
1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
7 YEAR 2 2 1997-98 1998-99 2 1998-99 2 1998-99 3 1999-2000 5 2001-02 6 2002-03 6 2002-03 8 2004-05 9 2005-06 11 2007-08
N